

**REQUEST FOR INFORMATION  
FOR  
COUNTY OF SAN MATEO**

**LISTED BELOW ARE THE QUESTIONS (Q) SUBMITTED BY  
POTENTIAL CONTRACTORS FOR THE  
FAIR OAKS LIBRARY DATA WIRING RFQ**

**THE COUNTY OF SAN MATEO DEPARTMENT OF PUBLIC WORKS HAS  
PROVIDED RESPONSES (R) TO THE QUESTIONS BELOW**

Q1. For the wireless, Is it a duplex outlet? I don't see it shown on the drawings.

*R1. The wireless has been completed in-house and is not part of this scope.*

Q2. For the card reader what type of cabling is needed for this reader?

*R2. The card reader portion is not part of this scope and will be done in-house.*

Q3. Are the cables for the card reader going to the IDF?

*R3. The card reader portion is not part of this scope and will be done in-house.*

Q4. The RFQ says to exclude cable tray or basket tray. Are we able to install J-hooks as needed to get to the tray?

*R4. The General Contractor's Electrical sub-contractor will be responsible for data rough-in such as conduits, junction boxes, raceway, wire basket tray, cable tray. General contractor will provide the path to all the data locations. Use J hook for ceiling mount to overhang the cables across the ceiling above the tiles wherever necessary.*

Q5. For the patch panels. There is room in the existing rack for the patch panels and wire management or are we to provide a rack?

*R5. Bidders will provide new materials similar or equivalent of 2 - 48 port CAT6 patch panels with 2-2u hinged patch panel brackets for easy access. Panduit wire manager 4-1/2 wide (3 horizontal mount and 1 vertical mount tiding the panels and the cisco switch.)*

Q6. Should patch cords be included? Is so, Patch panel side? Station side? How long?

*R6. Library IT will provide their own patch cords.*

Q7. Is there was a mandatory job walk, bid bond required and if there were any bid forms or just submit a quote to you.

*R7. No mandatory job walk was required, bid bond is not required, no bid forms are needed, quotes can be emailed to me by 4/3 @ 3 PM.*